





DATE: _____
FILE: _____



Provide at all interior bents without slab expansion joints.



(Rail Member showing Elliptical Tube Option,
Rectangular Tube Option similar).



The diagram illustrates the construction of a concrete slab and rail footprint. Key features include:

- Concrete Rail Footprint**: The top horizontal section of the concrete structure.
- Outside Edge of Slab or Abut Wingwall**: The left vertical boundary of the slab.
- Slab Expansion Joint**: A vertical dashed line indicating a joint in the slab.
- Concrete Rail Expansion Joint**: A vertical dashed line indicating a joint in the rail footprint.
- Location of Rail Expansion Joint**: A note stating that the location of the rail expansion joint must be at the intersection of the slab expansion joint, the rail footprint, and perpendicular to the slab outside edge.
- Rail Footprint**: The bottom horizontal section of the concrete structure.
- Cross-hatched area**: A diagonal hatched area between the slab and the rail footprint, which must contain $\frac{1}{2}$ " Preformed Bituminous Fiber Material under the concrete rail.
- Traffic Side of Rail**: The bottom horizontal section of the concrete structure, labeled as the traffic side.

Example showing Slab Expansion Joints without breakbacks.

- ① Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- ② Rail member sections must have at least two posts but not more than four.
- ③ One shop splice per rail member section is permitted with minimum 85 percent penetration. The weld may be square groove or single V groove. Grind smooth.
- ④ $\frac{1}{4}$ Exp Jt or Splice Jt as required.
- ⑤ Unless directed otherwise by the Engineer, the Fabricator may use the rectangular tube in lieu of the elliptical tube for the rail member.
- ⑥ Increase 2" for structures with overlay.
- ⑦ Place 4 additional Bars R(#5) 3'-8" in length inside Bars U(#5) and centered 2'-0" from end of rail when Terminal Connections are required. Field bend as needed.

SHEET 1 OF 3




Texas Department of Transportation

**Bridge
Division
Standard**


TRAFFIC RAIL

TYPE T402


FILE: RL-T402-19.dgn		DN: TxDOT	CK: TxDOT	DW: JTR	CK: JIM
 TxDOT September 2019 REVISIONS	CONT	SECT	JOB	HIGHWAY	
	DIST	COUNTY			SHEET N

DISCLAIMER:
The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE:
FILE:




SECTIONS THRU RAIL ⑤



ELLIPTICAL TUBE WITH RAIL POST & ANCHORAGE DETAILS

(Showing Elliptical Tube Option)



RECTANGULAR TUBE WITH RAIL POST & ANCHORAGE DETAILS ⑤

(Showing Rectangular Tube Option)

- ⑤ Unless directed otherwise by the Engineer, the Fabricator may use the rectangular tube in lieu of the elliptical tube for the rail member.
- ⑥ Increase 2" for structures with overlay.
- ⑧ 5 1/4" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.
- ⑨ See "Material Notes" for anchor bolt information.
- ⑩ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.

SHEET 2 OF 3




TRAFFIC RAIL

TYPE T402

FILE: RL-T402-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: JMH
©TxDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS				
	DIST	COUNTY		SHEET NO.


DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:



RECTANGULAR TUBE SLEEVE MEMBER DETAIL


(See Tube Fabrication Detail)



TUBE FABRICATION DETAILS ⑤


ELLIPTICAL TUBE & ELLIPTICAL SLEEVE MEMBER		
8" x 4 7/8" Ellipse	Elliptical Sleeve Member	
Material	Material	Thickness
6" Dia Std Pipe ASTM A53 E or S Gr B	ASTM A53 Gr B	0.353"
	ASTM A36 or A500 Gr B	0.339"
	API-5LX52	0.224"
6 5/8" O.D. Pipe x 0.188" API-5LX52	ASTM A53 Gr B	0.339"
	ASTM A36 or A500 Gr B	0.325"
	API-5LX52	0.188"

Notes: Other sections of equal or greater strength are acceptable for elliptical sleeves. The major and minor diameters of the rail member may vary +/- 0.1875" from plan dimension. However, the difference between the outside diameters of the elliptical sleeve and the inside diameters of the rail member must not exceed 0.25 inches.






OPTIONAL SIDE SLOT DRAIN DETAILS

Note: Center Side Slot Drains between rail posts within the limits shown. Side Slot Drains may be used where shown elsewhere on the plans or as directed by the Engineer. Do not place drains over railroad tracks, lower roadways, or sidewalks. When this rail is used as a separator between a roadway surface and a sidewalk surface, side drain slots will not be permitted.



CAST-IN-PLACE ANCHOR BOLT OPTIONS ⑨



Cover dimensions are clear dimensions, unless noted otherwise. Reinforcing bar dimensions shown are out-to-out of bar.

GENERAL NOTES:
This rail has been evaluated and approved to be of equal strength to railing with like geometry, which have been crash tested to meet MASH TL-4 criteria. This rail can be used for speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can only be used for speeds of 45 mph and less.
Do not use this railing on bridges with expansion joints providing more than 5" movement. Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.
Submit erection drawings showing panel lengths, rail post spacing, and anchor bolt setting, to the Engineer for approval.
Average weight of railing with no overlay: 343 plf total
313 plf (Conc)
30 plf (Steel).

MATERIAL NOTES:
Galvanize all metal components of steel rail system. Apply additional coatings when shown elsewhere on the plans. When plans require paint over galvanizing, follow the requirements for painting galvanized steel in Item 445, "Galvanizing" and when field painting, Item 446, "Field Cleaning and Painting Steel". Sleeve members and anchor bolts must receive galvanization prior to installation and only field paint after installation unless directed otherwise by Engineer.
Anchor bolts must be 7/8" Dia ASTM A193 Gr B7 fully threaded rods with heavy hex nuts, one hardened steel washer (ASTM F436), and one (2 1/4" O.D.) steel washer each. Nuts must conform to ASTM A563 requirements. Embed fully threaded rods into parapet wall with a Type III, Class C, D, E, or F anchor adhesive. Minimum adhesive anchor embedment depth is 8". Anchor adhesive chosen must be able to achieve a nominal bond strength in tension of a single anchor, Na, of 17 kips (edge distance must be accounted for). Submit signed and sealed calculations or the manufacturer's published literature showing the proposed anchor adhesive's ability to develop this load to the Engineer for approval prior to use. Anchor installation, including hole size, drilling, and clean out, must be in accordance with Item 450, "Railing."
Optional cast-in-place anchor bolts must be 7/8" Dia ASTM F3125 Gr A325 or A449 bolts (or A193 Gr B7 or F1554 Gr 105 threaded rods with one tack welded heavy hex nut each) with one heavy hex nut and one hardened steel washer (ASTM F436) plus one (2 1/4" O.D.) steel washer at each bolt. Nuts must conform to ASTM A563 requirements.
Provide Class "C" concrete. Provide Class "C" (HPC) if required elsewhere.
Provide Grade 60 reinforcing steel.
Epoxy coat or galvanize all reinforcing steel if slab bars are epoxy coated or galvanized. Deformed Welded Wire Reinforcement (WWR) ASTM A1064 may be substituted for Bars R, and V, as shown. Provide the same laps as required for reinforcing bars.
Provide bar laps, where required, as follows: Uncoated or galvanized ~ #5 = 2'-0"
Epoxy coated ~ #5 = 3'-0"

CONSTRUCTION NOTES:
This rail may be slipformed if approved by the Engineer when adhesive anchor bolts are used. At the Contractor's option anchor bolts may be cast with the parapet (See Cast-in-Place Anchor Bolt Options).
Slipforming parapet is not allowed if anchor bolts are cast with parapet wall.
If rail is slipformed, apply a heavy epoxy bead 1" behind toe of traffic side of rail to concrete deck just prior to slip forming. Provide a 3/8" width x 1/4" tall heavy epoxy bead with Type III, Class C or a Type V epoxy.
Test adhesive anchors in accordance with Item 450.3.3, "Tests". Test 3 anchors per 100 anchors installed. Perform corrective measures to provide adequate capacity if any of the tests do not meet the required test load. Repair damage from testing as directed.
Rail parapet must be plumb unless otherwise approved. Steel posts must be square to the top of parapet. Use Type VIII epoxy mortar under post base plates if gaps larger than 1/16" exist. Cap all ends of tubular steel sections at parapet.
Rail member sections must have at least two posts but not more than four.
Round or chamfer all exposed edges of steel components 1/16" by grinding prior to galvanizing. Chamfer all exposed concrete corners.

RAIL DATA FOR HORIZONTAL CURVES			
	RADIUS TO FACE OF RAIL	MAX CHORD LENGTH	CONSTRUCT OR FABRICATE
Rail Members	Over 2800'	29'-0"	Straight rail sections
	Over 1400' thru 2800'	14'-6"	To required radius or to chords shown ⑬
	Over 700' thru 1400'	7'-3"	
	Thru 700'	Zero	To required radius ⑬

Bridge Division Standard

TRAFFIC RAIL

TYPE T402

FILE: RL-T402-19.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: JMH
©TxDOT September 2019	CONT	SECT	JOB	HIGHWAY
REVISIONS				
	DIST	COUNTY		SHEET NO.